



# LK202-25

## *User Manual*



# Table of Contents

<b>1. Introduction .....</b>	<b>4</b>
1.1 What it Does .....	4
1.2 What it Does Not Do .....	4
1.3 Keypad Interface.....	4
1.4 Setup for Testing .....	4
1.5 Trying Out your LK202-25 .....	5
1.6 Trying out a Keypad.....	6
1.6.1 Here's what to do: .....	6
1.7 To Reset the module .....	7
<b>2. Connections.....</b>	<b>8</b>
2.1 Connector Pinout .....	8
2.1.1 Power and I <sup>2</sup> C Connections .....	8
2.1.2 RS-232 Communications .....	10
2.2 General Purpose Outputs.....	10
<b>3. Displaying Text.....</b>	<b>13</b>
3.1 General .....	13
3.2 The Built-In Character Font.....	13
3.3 Writing Text to the Display .....	14
3.4 Text Commands .....	14
3.4.1 Auto line wrap on (254 67) (R) .....	14
3.4.2 Auto line wrap off (254 68) (R) .....	14
3.4.3 Auto scroll on (254 81) (R).....	14
3.4.4 Auto scroll off (254 82) (R).....	14
3.4.5 Set cursor position (254 71 [column] [row]) .....	14
3.4.6 Send cursor home (254 72).....	14
3.4.7 Turn on underline cursor (254 74) (R) .....	15
3.4.8 Turn off underline cursor (254 75) (R) .....	15
3.4.9 Turn on block (blinking) cursor (254 83) (R).....	15
3.4.10 Turn off block (blinking) cursor (254 84) (R) .....	15
3.4.11 Cursor left (254 76).....	15
3.4.12 Cursor right (254 77).....	15
<b>4. Keypad Interface .....</b>	<b>16</b>
4.1 General .....	16
4.2 Connections .....	16
4.3 I <sup>2</sup> C Interface.....	17
4.4 RS-232 Interface .....	17
4.5 Keypad Commands .....	17
4.5.1 Auto repeat mode on (254 126 [mode]) (R) .....	17
4.5.2 Auto repeat mode off (254 96) (R).....	18
4.5.3 Auto transmit keypresses on (254 65) (R).....	18
4.5.4 Auto transmit keypresses off (254 79) (R) .....	18
4.5.5 Clear key buffer (254 69) .....	18
4.5.6 Poll keypad (254 38).....	18
4.5.7 Set debounce time (254 85 [time]) (R) .....	18

<b>5. Bar Graphs and Special Characters.....</b>	<b>19</b>
5.1 Command List.....	19
5.1.1 Initialize wide vertical bar graph (254 118) .....	19
5.1.2 Initialize narrow vertical bar graph (154 115).....	19
5.1.3 Draw vertical bar graph (254 61 [column] [height]) .....	19
5.1.4 Initialize horizontal bar graph (254 104).....	19
5.1.5 Draw horizontal bar graph (254 124 [column] [row] [dir] [length]) .....	19
5.1.6 Define custom character (254 78 [c] [8 bytes]).....	19
<b>6. Miscellaneous Commands .....</b>	<b>21</b>
6.1 Command List.....	21
6.1.1 Remember (254 147 [0 1]) .....	21
6.1.2 Clear display (254 88).....	21
6.1.3 Set contrast (254 80 [contrast]) .....	21
6.1.4 Set contrast and save (254 145 [contrast]) .....	21
6.1.5 Backlight on (254 66 [minutes]) (R).....	22
6.1.6 Backlight off (254 70) (R).....	22
6.1.7 Load startup screen (254 64 [40 characters]) .....	22
6.1.8 General purpose output off (254 86 [gpo #]) .....	22
6.1.9 General purpose output on (254 87 [gpo #]) .....	22
6.1.10 Set I <sup>2</sup> C address 254 51 [address]) .....	22
6.1.11 Read module type (254 55).....	23
6.1.12 Set RS232 port speed (254 57 [speed]) .....	23
6.1.13 Set Serial Number (254 52 [byte1] [byte2]).....	23
6.1.14 Read Serial Number (254 53) .....	23
6.1.15 Read Version Number 254 54) .....	24
6.2 Flow Control.....	24
6.2.1 Enter Flow Control Mode (254 58 [full][empty]) .....	24
6.2.2 Exit Flow Control Mode (254 59) .....	24
<b>7. Appendix: Command Summary .....</b>	<b>25</b>
7.1 General .....	25
7.2 Issuing Commands.....	25
7.3 On Numbers .....	25
7.3.1 ASCII Characters.....	26
7.4 Text Commands .....	26
7.5 Keypad Interface Commands.....	27
7.6 Bar Graphs and Special Characters .....	28
7.7 Miscellaneous Commands.....	29
<b>8. Appendix: Specifications and Options.....</b>	<b>31</b>
8.1 Specifications .....	31
8.2 Options .....	32
<b>9. Appendix: Glossary.....</b>	<b>33</b>
<b>10. List of Distributors.....</b>	<b>35</b>

# 1. Introduction

Your LK202-25 has the following features:

- 20 column by 2 line text display
- built-in font with provision for up to 8 user-defined characters
- Speeds from 1200 bps to a lightning fast 19.2 Kbps over RS232
- Communicate over RS232 or I<sup>2</sup>C
- Use up to 16 modules on the same 2-wire I<sup>2</sup>C interface
- Fully buffered so that no delays in transmission are ever necessary
- Add your own Splash/Start-up screen
- Use our "Remember" functions to save settings
- Software controlled contrast, backlight with configurable time-out setting up to 180 minutes and software controlled speed
- Use up to a 25 key keypad with a 10 key buffer.
- Six general purpose outputs for a variety of applications
- Horizontal or Vertical bar graphs
- Variable power options, +5V or +9V to +15V
- Extended temperature option.
- Fits our PC Bay inserts without any modifications

## 1.1 What it Does

The LK202-25 is designed as the display unit for an associated controller. The controller may be anything from a single board, special purpose microcontroller to a PC, depending on the application. This controller is responsible for what you see on the screen of the LK202-25.

The LK202-25 provides a simple command structure to allow text and bar graphs to be displayed on the screen. Text fonts are built in, and use standard ASCII mapping. Provision is made for up to 8 user-defined characters.

The screen is backlit for low-light situations. Backlighting may be turned on or off under program control. Contrast is adjustable to compensate for differing lighting conditions and viewing angles.

General purpose outputs allow the controller to switch up to six electronic or electro-mechanical devices by issuing commands to the display unit. These can be used for controlling LEDs, relays, etc.

## 1.2 What it Does Not Do

The LK202-25 does not include bitmap graphics capability, except that permitted by defining special characters.


## 1.3 Keypad Interface

The keypad interface takes row/column input and converts it to ASCII characters, which are delivered out the RS-232 or I<sup>2</sup>C port to the associated controller. Note that the keypad is **not** used to directly control any aspect of the operation of the LK202-25, which acts simply as a matrix to serial converter. If you want to use the keypad to control the LK202-25 display you must program your controller accordingly.

## 1.4 Setup for Testing

Before setting up your application you may want to try out the LK202-25. This is easily done with a PC. Here's what you'll need:

- A power cable with a 4 pin connector (same connector as used to connect 3.5 inch floppy drive). Do not connect the LK202-25 to an unmodified spare power connector in a PC. To modify such a cable see section 2.1.1.
- A 5 V power supply.
- a PC with a spare RS-232 port (COM1 or COM2).
- A 9 or 25 pin RS-232 serial cable. If you use a 25 conductor cable you'll also need a 9 to 25 pin adapter.



*Figure 1-1 Connections for Testing*

1. Refer to the diagram above and Figure 2-1 for the following steps.
2. Wire the connector to the power supply. On most connectors the RED lead will go to +5V and the BLACK lead to GND. See Section 2.1.1 for details. **Note: The manufacturer's warranty is void if the unit is subjected to over-voltage or reversed polarity.**
3. Connect the LK202-25 to the PC using the serial cable and adapter if required. **Make sure the RS-232 cable includes the required ground lead. There must be no voltage differential between the RS-232 ground and the power supply ground.**
4. Connect the power connector, making sure that the +5V goes to V+ as shown in Figure 2-2. Turn on the power: the LCD backlight should come on.

Now you're ready to try it out.

## 1.5 Trying Out your LK202-25

The unit is connected to power and the PC and the backlight is on. You're ready to make sure it's working properly.

- To experiment with typing text, run a PC terminal program, such as Hyperterm. Make sure it's configured to use the correct port. Set the baud rate to 19,200.

If you type characters on the keyboard, they should now appear on the LK202-25 screen. Text will wrap around to the next line when you reach the end of a line. A few common ASCII control characters work as follows:

Character	Hex value	Function
CR	0x0D	Moves cursor to beginning of the current line.
LF	0x0A	Moves cursor to the beginning of the next (or previous) line.
FF	0x0C	Clears the display and puts the cursor at the top left
BS	0x08	Moves the cursor one position to the left and clears that position.

---

**Note: These command characters are not guaranteed to work on other Matrix Orbital display modules. If you want your code to be portable, use the appropriate commands listed later in the manual instead.**

---

If you want to exercise some of the other features of the LK202-25 you'll need to write a program (in any convenient language such as Basic or C) to issue the required command strings. Most terminal programs are unable to issue the 0xFE character needed as a command prefix. You probably won't need to do this at the initial testing stage.

If you've reached this point and operation is normal, you can be confident that your LK202-25 works properly.

## 1.6 Trying out a Keypad

Since a number of different keypad types can be connected to the LK202-25, the results you get may be a little unpredictable. At this point all we need to do is make sure that your keypad and interface work, and possibly generate an ASCII map for your programming needs.

The keypad interface on the LK202-25 converts a row/column connection to an ASCII character. By default, a keypress is transmitted as serial data immediately. Keypad buffering can be selected using the appropriate commands.

### 1.6.1 Here's what to do:

1. Your PC should be running a terminal program, such as Hyperterm (as in the previous section).
2. With the LK202-25 connected to the PC, plug in your keypad. If your connector has fewer pins than the one on the LK202-25, center it as well as possible.

---

**Note 1:** The keypad connector must be wired with columns on one side and rows on the other side of the center of the connector. If your keypad isn't wired this way you will need to make an adapter or rewire the connector to meet this requirement.

**Note 2:** The connector is reversible. Reversing the connector will not damage the keypad or the LK202-25, but it will change the ASCII character map.

---

3. Press a key on the keypad. An upper case ASCII character (A-Y) should appear on the PC screen. Different keys should generate different characters.

If you want to experiment, reverse the connector and see if it generates a more logical set of characters. Ultimately, the program in your controller will have to "map" these characters to the ones marked on the keypad, which will likely be different.

## 1.7 To Reset the module

Manual override should only be required in one instance. If for some reason the module is set at a baud rate which cannot be produced by the host system and all communication to the display is lost, then the user should follow this simple procedure:

1. Turn off the display
2. Put a jumper on pins 5 and 6 of the keypad connector (C5 and R1).
3. Power up the display. The baud rate is now set to 19,200.
4. Remove the jumper and change the RS-232 port settings to the desired baud rate.
5. Turn off the display.
6. Power up the display.

Refer to the “Set RS-232 Port Speed” command (section 6.1.12) for acceptable baud rates.

## 2. Connections

### 2.1 Connector Pinout

Refer to the diagram below for this chapter.




Figure 2-1 Electrical Connections

The LK202-25 has four connectors:

<u>Connector</u>	<u>Function</u>
14 pin dual header	General purpose outputs (6) (see section 2.2)
4 pin	power (5.0 VDC) and I <sup>2</sup> C communications (see section 2.1.1)
10 pin header	Keypad (see section 3.4.12)
DB-9F	RS-232/power (see section 2.1.1.1)

#### 2.1.1 Power and I<sup>2</sup>C Connections

Power is applied via pins 1 and 4 as shown in Figure 2-1. Power requirement is +5 VDC  $\pm$ 0.25V. Power may also be supplied via the RS-232 connector as described in the next section.

### **Warning:**

- Do not apply any power with reversed polarization.
- Do not apply any voltage other than the specified voltage.
- Do not use any cables other than the cables supplied by Matrix Orbital, unless you are aware of the modifications required.

Connector pinout is as follows:



Figure 2-2 Power connector

Pin 1	+5.0 VDC (+7 to +15 VDC with wide voltage option)
Pin 2	SCL (I <sup>2</sup> C clock)
Pin 3	SDA (I <sup>2</sup> C data)
Pin 4	Ground

### 2.1.1.1 Five Volt Modules

If the LK202-25 is used in a PC it is tempting to plug a spare power connector into the unit. **Don't do this!** Wiring for the PC power connector and that required for the LK202-25 are different as shown in Figure 2-3 below.




Figure 2-3 Power Connector wiring differences

If you don't want to modify cable wiring yourself, Matrix Orbital can supply an adapter cable designed to use with the LK202-25 when it's installed in a PC. The cable is wired as shown in Figure 2-4 below. Note that this cable does not provide connections for I<sup>2</sup>C.




Figure 2-4 Five volt Power Cable

### 2.1.1.2 Wide Voltage Range Modules

---

Note: Do not use this cable unless your display module has the "wide voltage range" option (option V). Use of the 12 volt power cable with 5 volt modules will damage the module.

---

The 12 volt power cable is designed for use with wide voltage range display modules mounted in a PC. Wiring required for the 12 volt power connector is shown in Figure 2-5 below.




Figure 2-5 Wiring for 12 volt modules

If you don't want to modify cable wiring yourself, Matrix Orbital can supply an adapter cable designed to use with the display module when it's installed in a PC. The cable is wired as shown in Figure 2-6 below.




Figure 2-6 Twelve volt power cable

### 2.1.2 RS-232 Communications

A standard DB-9F is provided for RS-232 communications. Power may also be supplied via this connector if desired. See Figure 2-7 for pin connections.




Figure 2-7 RS-232 and power connector

The RS-232 connector on the PC cable is wired so that a standard “straight through” 9 pin D-sub cable may be used to connect the module to a standard serial port such as COM ports on PCs. Note that this device complies with the EIA232 standard in that it uses signal levels from +/- 3V to +/- 12V. It will not operate correctly at TTL (0 to +5V) levels.

Pin Number	Direction	Description
2	from LCD module	Data Out
3	to LCD module	Data In
5	-	Ground

The power connector on the PC cable is wired as shown in Figure 2-7.

## 2.2 General Purpose Outputs

The LK202-25 has six general purpose outputs. These are provided to control relays or other electronic devices. This allows external devices to be turned on or off using your PC or controller and software commands. (See sections 6.1.8 and 6.1.9 for the command syntax.)

Each output is wired as shown in Figure 2-8. The + terminal is connected directly to the module positive supply, the – terminal is connected through a 240 ohm current limiting resistor and the electronic switch to ground.




Figure 2-8 General Purpose Outputs

Maximum allowable current is 20 mA, which is enforced by the current limiting resistor. If the device being switched has a resistance of 240 ohms or more the corresponding resistor may be shorted. Solder a small jumper wire (wirewrap wire is good) from the feedthrough hole to the corresponding negative pin for the GPO in question.





Figure 2-9 Bypassing 240 ohm resistor

---

Note: The GPOs do not have any over current or over/under voltage protection so care must be taken when using them. For instance if the external device is a relay it must be fully clamped (using a diode and capacitor) to absorb any generated back electro-motive force (EMF).

---



*Figure 2-10 Clamping a Relay*

### 3. Displaying Text

This chapter describes the various text-display commands in detail. A quick reference summary of all text commands is found in section 7.4.

#### 3.1 General

Text is displayed on the LK202-25 using the built-in 5 x 7 dot matrix font (plus up to 8 user-defined characters).

#### 3.2 The Built-In Character Font

The LK202-25 includes a built-in 5 x 7 dot matrix font with the full range of ASCII characters plus a variety of extended characters, as shown in Figure 3-1.

				D7	0	0	0	0	0	0	0	0	1	1	1	1	1	1	1		
				D6	0	0	0	0	1	1	1	1	0	0	0	0	1	1	1	1	
				D5	0	0	1	1	0	0	1	1	0	0	1	1	0	0	1	1	
				D4	0	1	0	1	0	1	0	1	0	1	0	1	0	1	0	1	0
D3	D2	D1	D0	0	1	2	3	4	5	6	7	8	9	A	B	C	D	E	F		
0	0	0	0	0				0aP`P						-	9	E	O	P			
0	0	0	1	1				!1A0aA						#	7	7	4	a	9		
0	0	1	0	2				"2BRbr						r	i	u	x	B	B		
0	0	1	1	3				#3CScs						l	o	7	e	e	*		
0	1	0	0	4				\$4DTdt						\	I	t	f	H	Q		
0	1	0	1	5				%5EUeu						.	a	+	i	c	Q		
0	1	1	0	6				&6FUfv						7	+	+	+	+	+		
0	1	1	1	7				'7GUgw						7	+	7	7	7	7		
1	0	0	0	8				(8HXhx						4	o	7	u	r	x		
1	0	0	1	9				)9IYiy						e	7	u	u	u	u		
1	0	1	0	A				*:JZjz						E	o	n	v	u	7		
1	0	1	1	B				+;K[k<						*	7	e	o	'	7		
1	1	0	0	C				,<L#ll						7	7	7	7	7	7		
1	1	0	1	D				-=Mln>						u	7	7	7	7	7		
1	1	1	0	E				.>N^n+						e	e	7	7	7	7		
1	1	1	1	F				/?O_lo+						w	u	7	7	7	7		

Figure 3-1 Character Set

In addition to the built-in characters, users may define up to 8 special characters (which, once defined, occupy positions 0x00 to 0x07 in the above chart). The LK202-25 does not have provision to download other fonts.

### 3.3 Writing Text to the Display

When the display receives a character, it displays that character at the position currently defined. The next character sent to the module then advances to the following position on the display. Characters are drawn using the built-in font, and only characters defined in the font are actually displayed. Characters that are not defined by the built-in font print as a space (i.e. the cursor is advanced for the next character).

The position where text is to be inserted is a character location stored in the LK202-25's volatile memory and maintained internally by the LK202-25's firmware. This position is manipulated by the commands shown in the following section.

### 3.4 Text Commands

In this section commands are identified by their names and decimal values. Hex and ASCII equivalents are given in the summary (Table 7-1). **Before issuing commands to the LK202-25 please read sections 7.2 and 7.3.**

Some commands, marked with an (R), may be "remembered" to set new defaults that will be in effect each time the unit is powered on. See section 6.1.1 for further information.

#### 3.4.1 Auto line wrap on (254 67) (R)

Enables automatic line wrapping. Note that this is not "word wrapping" and wraps may occur in the middle of a word.

#### 3.4.2 Auto line wrap off (254 68) (R)

Disables automatic line wrapping. Characters beyond the end of a line will be lost.

#### 3.4.3 Auto scroll on (254 81) (R)

When auto scrolling is on, it causes the LK202-25 to shift the entire display's contents up to make room for a new line of text when the text reaches the scroll position (the bottom right character position).

#### 3.4.4 Auto scroll off (254 82) (R)

When auto scrolling is disabled, text will wrap to the top left corner of the display area. Existing text in the display area is not erased before new text is placed. A series of "spaces" followed by a Cursor Home command may be used to erase the top line of text.

#### 3.4.5 Set cursor position (254 71 [column] [row])

This command sets the cursor position (text insertion point) to the [column] and [row] specified. Columns have values from 1 to 20 (0x01 to 0x14) and rows have values of 1 and 2 (0x01 and 0x02).

#### 3.4.6 Send cursor home (254 72)

This command moves the cursor position (text insertion point) to the top left of the display area.

### 3.4.7 Turn on underline cursor (254 74) (R)

Turns on the underline cursor. The cursor shows the current text insertion point. Both underline and blinking cursors may be turned on or off independently. The cursor is off by default.

### 3.4.8 Turn off underline cursor (254 75) (R)

Turns off the underline cursor. Does not affect the blinking block cursor.

### 3.4.9 Turn on block (blinking) cursor (254 83) (R)

Turns on the blinking block cursor. The cursor shows the current text insertion point. Both blinking and underline cursors may be turned on or off independently. The cursor is off by default.

### 3.4.10 Turn off block (blinking) cursor (254 84) (R)

Turns off the blinking block cursor. Does not affect the underline cursor.

### 3.4.11 Cursor left (254 76)

Moves the cursor one position to the left but does not erase any character that may be in that position. Note that this command moves the text insertion point even if the cursor is turned off.

---

Note: A "destructive backspace", which erases the character to the left of the original position, may be done by issuing the following sequence: cursor left, space, cursor left.

---

### 3.4.12 Cursor right (254 77)

Moves the cursor one position to the right but does not erase any character that may be in that position. Note that this command moves the text insertion point even if the cursor is turned off.

## 4. Keypad Interface

This chapter describes the keypad interface and associated commands in detail.

### 4.1 General

The LK202-25 keypad interface processes the keypad row/column matrix into a serial (RS-232 or I<sup>2</sup>C) data byte stream. Aside from this processing, the keypad has no effect on the LK202-25 display. If you need to send keystrokes to the display, they must be routed through your controller.

### 4.2 Connections




Figure 4-1 Keypad Connector

The connector is not "keyed" so your keypad will probably plug in either of two ways. The LK202-25 will not be damaged by reversing the connector, but your keypad will generate a different ASCII character mapping for each position. If your connector has fewer than 10 pins it should be centered on the LK202-25 connector.

The returned key codes are as follows, but note that your keypad may be laid out in a different pattern. If this is the case, you will need to interpret the key codes differently. The diagram 1 shows the logical layout (row 1, column 1 in upper left). The connector for the keypad is a 10 pin 0.1" spacing male header. Pin 1 is indicated in Figure 2-1. Pins 1 through 5 are columns and pins 6 through 10 are rows. The keypad is scanned whenever a key is pressed: there is no continuous key scan. This means that key presses are dealt with immediately without any appreciable latency. This also prevents electrical noise which is often caused by continuous key scans.

		Columns				
		1	2	3	4	5
Rows	1	A	B	C	D	E
	2	F	G	H	I	J
	3	K	L	M	N	O
	4	P	Q	R	S	T
	5	U	V	W	X	Y

---

**Note:** The keypad connector must be wired with columns on one side and rows on the other side of the center of the connector. If your keypad isn't wired this way you will need to make an adapter or rewire the connector to meet this requirement.

---

## 4.3 I<sup>2</sup>C Interface

The keypad is read by I<sup>2</sup>C master read. In short, this means that a read of the module will always return the first unread key press. A read is initiated by writing to the module with its base address plus 1, then clocking the module's return byte after the module releases the SDA line. Much more detail on this basic I<sup>2</sup>C function can be found in the I<sup>2</sup>C specification by Philips. A good reference is also available at

<http://www.ping.be/~ping0751/i2cfaq/i2cindex.htm>

The module contains a ten key press buffer so that it can be polled for key presses at an infrequent rate (every 500 to 1000 mS is typical). All returned key presses indicate the presence or absence of additional logged key presses by the most significant bit (MSB - bit 7). If the user has pressed two keys since the last poll of the keypad interface, the first read will return the key code with bit 7 set and the second read will return the key code with bit 7 clear. The application must take into account this bit to keep up with user key presses. If there are no keypresses detected, the module will return zero (0x00).

## 4.4 RS-232 Interface

By default on any press of a key, the module will immediately send out the key code at the selected baud rate. This behavior can be modified using commands found in the next section.

## 4.5 Keypad Commands

**Before issuing commands to the LK202-25 please read sections 7.2 and 7.3.**

Some commands, marked with an (R), may be "remembered" to set new defaults that will be in effect each time the unit is powered on. See section 6.1.1 for further information.

### 4.5.1 Auto repeat mode on (254 126 [mode]) (R)

[mode] = 0x00 gives Resend Key Code mode

[mode] = 0x01 gives Key down / Key up code mode

Two Modes of auto repeat are available and are set via the same command.

1. **Resend Key Code:** This mode is similar to the action of a keyboard on a PC. In this mode, when a key is held down, the key code is transmitted immediately followed by a 1/2 second delay. After this delay, key codes will be sent via the RS - 232 interface at a rate of about 5 codes per second. This mode has no effect if polling or if using the I<sup>2</sup>C interface.
2. **Key down / Key up codes:** This mode may be used when the typematic parameters of the Resend Key code mode are unacceptable or if the unit is being operated in polled mode. The host system detects the press of a key and simulates an auto repeat inside the host system until the key release is detected.

In this mode, when a key is held down, the key code is transmitted immediately and no other codes will be sent until the key is released. On the release of the key, the key release code transmitted will be a value equal to the key down code plus 20 hex. For example, the key code associated with key 'P' (0x50) is pressed, the release code is 'p' (0x70).

In RS-232 polled mode (see 4.5.4 below) or via the I<sup>2</sup>C interface, the key down / key up codes are used; however, the user should be careful of timing details. If the poll rate is slower than the simulated auto - repeat it is possible that polling for a *key up* code will be delayed long enough for an unwanted key repeat to be generated (see Figure 4-2).




Figure 4-2 Poll timing

#### 4.5.2 Auto repeat mode off (254 96) (R)

This command turns off auto repeat mode.

#### 4.5.3 Auto transmit keypresses on (254 65) (R)

In this mode, all keypresses are sent immediately to the host system without the use of the poll keypad command. This is the default mode on power up.

#### 4.5.4 Auto transmit keypresses off (254 79) (R)

In this mode, up to 10 keypresses are buffered until the unit is polled by the host system via the poll keypad command. Issuing this command places the unit in *polled mode*.

#### 4.5.5 Clear key buffer (254 69)

This command clears any unread keypresses. In a menuing application, if the user presses a key which changes the menu context, any following key presses may be inaccurate and can be cleared out of the buffer between menu changes to prevent jumping around the menu tree. It may also be used to, in effect, reset the keypad in case the host application resets for whatever reason.

#### 4.5.6 Poll keypad (254 38)

This command returns any unbuffered keypresses via the RS - 232 interface. The host system must be set up to receive the key codes. When the LK202-25 receives this command it will immediately return any unbuffered keypresses which may have not been read already. If there is more than one keypress buffered, then the high order bit (MSB) of this returned keycode will be set (1). If this is the only buffered keypress, then the MSB will be reset (0). If there are no buffered keypresses, then the returned code will be 0x00. Please note to make use of this command the "Auto Transmit Keypress" mode should be off.

#### 4.5.7 Set debounce time (254 85 [time]) (R)

[time] is in increments of 6.554 milliseconds.

This command sets the time between key press and key read. All key types with the exception of latched piezo switches will "bounce" for a varying time, depending on their physical characteristics. The default debounce time for the module is about 52 mS, which is adequate for most membrane keypads. This time equates to a setting of 8 using this command as there is a debounce time resolution of 6.554 milliseconds.

## 5. Bar Graphs and Special Characters

The LK202-25 includes the ability to draw bar graphs (either horizontal or vertical) and allows users to define up to eight special characters. **Before issuing commands to the LK202-25 please read sections 7.2 and 7.3.**

Eight characters (ASCII values 0x00 to 0x07) are set aside for use with bar graphs, user defined characters, and big numbers. Since the same 8 characters are used for each function, the functions may not be used simultaneously. The characters may be defined or redefined at any time by issuing the commands shown in this section. Once defined, they may be used either by means of the bar graph commands, or by simply issuing one of the ASCII values 0x00 to 0x07 (which is not prefixed by the command byte, 254).

### 5.1 Command List

#### 5.1.1 Initialize wide vertical bar graph (254 118)

This command defines the 8 special/user characters to be blocks suitable for use in drawing wide (5 pixel) vertical bar graphs. Any previously existing definitions will be lost. Once this command has been issued, any number of vertical bar graphs may be drawn unless the characters are redefined by another command.

#### 5.1.2 Initialize narrow vertical bar graph (154 115)

This command defines the 8 special/user characters to be blocks suitable for use in drawing narrow (2 pixel) vertical bar graphs. Any previously existing definitions will be lost. Once this command has been issued, any number of vertical bar graphs may be drawn unless the characters are redefined by another command.

#### 5.1.3 Draw vertical bar graph (254 61 [column] [height])

Draws a vertical bar graph in [column] having a height of [height] pixels. The height may range from 0 to 20 (0x00 to 0x14) pixels. The necessary characters must first be initialized by either of the commands shown in section 5.1.1 or 5.1.2, which will determine the width of the graph drawn. Graph may be erased by drawing a bar graph of height = 0 in the same column.

#### 5.1.4 Initialize horizontal bar graph (254 104)

This command defines the 8 special/user characters to be blocks suitable for use in drawing horizontal bar graphs. Any previously existing definitions will be lost. Once this command has been issued, any number of horizontal bar graphs may be drawn unless the characters are redefined by another command.

#### 5.1.5 Draw horizontal bar graph (254 124 [column] [row] [dir] [length])

Draws a horizontal bar graph in [row] starting at [column] with a length of [length] pixels. [row] may have a value of 0x01 or 0x02, column may range from 0x01 to 0x14 and length may be from 0x00 to 0x64 (0 to 100) if the graph can extend the full width of the screen. Each column is 5 pixels wide (spaces between the columns don't count).

[dir] specifies the direction: 0x00 goes from left to right, 0x01 goes from right to left.

#### 5.1.6 Define custom character (254 78 [c] [8 bytes])

The LK202-25 allows up to 8 user defined (custom) characters. These characters occupy the first 8 (0x00 to 0x07) places in the character set (see Figure 3-1).

Custom characters occupy a 5 x 8 pixel matrix. Built-in characters are 5 x 7: the bottom row of pixels is normally reserved for the underline cursor. The underline cursor should be turned off if the bottom row of pixels forms part of a custom character.

The characters are defined by issuing the command 254 78 [c] followed by 8 bytes to define the character. [c] is the character number (0x00 to 0x07). The 8 bytes are mapped as shown below:

MSB			LSB					
*	*	*	1	2	3	4	5	Data Byte 1
*	*	*	6	7	8	9	10	Data Byte 2
*	*	*	11	12	13	14	15	Data Byte 3
*	*	*	16	17	18	19	20	Data Byte 4
*	*	*	21	22	23	24	25	Data Byte 5
*	*	*	26	27	28	29	30	Data Byte 6
*	*	*	31	32	33	34	35	Data Byte 7
*	*	*	36	37	38	39	40	Data Byte 8

A "1" bit indicates an on (black) pixel, a "0" bit indicates an off (clear) pixel.

Once defined, a character is displayed simply by issuing a value (0x00 to 0x07) corresponding to the character number. The character will be laid out as follows:

1	2	3	4	5
6	7	8	9	10
11	12	13	14	15
16	17	18	19	20
21	22	23	24	25
26	27	28	29	30
31	32	33	34	35
36	37	38	39	40
Cursor Line				

---

Note: Custom characters will be erased if any of the "initialize bar graph" commands are issued.

---

## 6. Miscellaneous Commands

The commands listed in this chapter don't readily fit in any of the other categories, or are used in more than one category. **Before issuing commands to the LK202-25 please read sections 7.2 and 7.3.**

Some commands, marked with an (R), may be "remembered" to set new defaults that will be in effect each time the unit is powered on. See section 6.1.1 for further information.

### 6.1 Command List

#### 6.1.1 Remember (254 147 [0|1])

This command allows a number of settings, such as cursor state, backlight, etc. to automatically be stored to non-volatile memory so they become new defaults. The command should only be used when required for two reasons:

1. Writing to non-volatile memory is time consuming and slows down the operation of the display.
2. Non-volatile memory has a "write limit" and may only be changed approximately 100,000 times.

Commands which may be used with the "remember" function are marked with an "R" in the "default" column in the command tables.

The example shows the procedure to set Auto scroll ON as the default condition. Commands are shown in both decimal and hex in this example.

<u>Decimal</u>	<u>Hex</u>	<u>Function</u>
254 147 1	FE 93 01	Turn on "remember" function.
254 81	FE 51	Turn on auto scroll. Since "remember" is ON, this setting will be saved in non-volatile memory.
254 147 0	FE 93 00	Turn off "remember" function.

Any number of commands may be entered between the "remember ON" and "remember OFF" commands, and all settings will be memorized.

#### 6.1.2 Clear display (254 88)

This command clears the display and resets the text insertion point to the top left of the screen.

#### 6.1.3 Set contrast (254 80 [contrast])

This command sets the display's contrast to [contrast], where [contrast] is a value between 0x00 and 0xFF (between 0 and 255). Lower values cause "on" elements in the display area to appear lighter, while higher values cause "on" elements to appear darker.

Lighting conditions will affect the actual value used for optimal viewing. Individual LK202-25 modules will also differ slightly from each other in appearance. In addition, values for optimal viewing while the LK202-25 backlight is on may differ from values used when backlight is off.

#### 6.1.4 Set contrast and save (254 145 [contrast])

This command works in exactly the same way as the "Set Contrast" command. The only difference is that it saves the contrast value in the non-volatile memory of the module, whereas the previous command only changes the value until the next power down.

### 6.1.5 Backlight on (254 66 [minutes]) (R)


This command turns on the backlight for a time of [minutes] minutes. If [minutes] is zero (0), the backlight will remain on indefinitely. Note: the factory default for backlight is on.

### 6.1.6 Backlight off (254 70) (R)


This command turns the backlight of the LK202-25 off.

### 6.1.7 Load startup screen (254 64 [40 characters])

This command sets and memorizes the startup screen that will appear each time the LK202-25 is turned on. By default the screen shows:



The 40 characters define the two 20 character rows of the screen. They may be any characters from the character set shown in Figure 3-1.



### 6.1.8 General purpose output off (254 86 [gpo #])

This command turns OFF any of the General Purpose Outputs (see section 2.2 for a description of the GPOs). [gpo #] is 1 to 6. Note that OFF means that the output floats.

### 6.1.9 General purpose output on (254 87 [gpo #])

This command turns ON any of the General Purpose Outputs. [gpo #] is 1 to 6. ON means that the output is pulled low (ground via 240 ohms).

### 6.1.10 Set I<sup>2</sup>C address 254 51 [address]

This command sets the I<sup>2</sup>C write address of the module. This value must be an even number and the read address is one higher. For example if the I<sup>2</sup>C write address is set to 0x50, then the read address is 0x51. The change in address is immediate. This address is 0x50 by default, and is reset temporarily back to that value when the "Manual Over-ride" jumper is used on power up (see section 1.7).

### 6.1.11 Read module type (254 55)

This command will return, over the RS-232 interface, the model type value of the module. Values for various modules at the time of this publication are as follows:

LCD0821 - 0x01	LCD2021 - 0x03	LCD1641 - 0x04
LCD2041 - 0x05	LCD4021 - 0x06	LCD4041 - 0x07
<b>LK202-25 - 0x08</b>	LK204-25 - 0x09	LK404-55 - 0x0A
VFD2021 - 0x0B	VFD2041 - 0x0C	VFD4021 - 0x0D
VK202-25 - 0x0E	VK204-25 - 0x0F	GLC12232 - 0x10
GLC12864 - 0x11	GLC128128 - 0x12	GLC24064 - 0x13
GLK12864-25 - 0x14	GLK24064-25 - 0x15	GLK128128-25 - 0x21
GLK12232-25 - 0x22	LK404-AT - 0x31	VFD1621 - 0x32
LK402-12 - 0x33	LK162-12 - 0x34	LK204-25PC - 0x35

### 6.1.12 Set RS232 port speed (254 57 [speed])

This command sets the GLK's RS232 port to the specified [speed]. The change takes place immediately. [speed] is a single byte specifying the desired port speed. Valid speeds are shown in the table below. The GLK can be manually reset to 19,200 baud in the event of an error during transmission (including transmitting a value not listed below) by setting the "manual override" jumper on the GLK controller board during power up (see section 1.7). This command is ignored until this jumper is removed again.

Speed Value	Speed
FF Hex	1200 baud
81 Hex	2400 baud
20 Hex	9600 baud
<b>0F Hex</b>	<b>19200 baud</b>

### 6.1.13 Set Serial Number (254 52 [byte1] [byte2])

Modules may be delivered with the serial number blank. In this case the user may set the desired 2 byte serial number using this **one time only** command.

Upon the execution of this command, the module will echo these two bytes back over the RS-232 interface. The serial number may be set only once. Any future attempt to execute this command will result in no change and the module will return to the originally set serial number.

### 6.1.14 Read Serial Number (254 53)

This command will return, over the RS-232 interface, the serial number of the module as it was previously stored.

### 6.1.15 Read Version Number (254 54)

This command will return the firmware version number of the LK202-25.

## 6.2 Flow Control

The LK202-25 has built-in flow control which may be useful when long strings of text are downloaded to the display. Flow control is enabled or disabled by two commands (see Table 7-4 and the next two sections). If flow control is enabled, the LK202-25 will return an "almost full" message (0xFE) to the controller when its internal buffer fills to a defined level, and an "almost empty" message (0xFF) when the buffer contents drop to a defined level.

### 6.2.1 Enter Flow Control Mode (254 58 [full][empty])

---

Note: Flow control applies only to the RS-232 interface. It is not available for I<sup>2</sup>C.

---

This command enables flow control. When the buffer fills so that only [full] bytes are available the LK202-25 will return an "almost full" message (0xFE) to the controller. When the buffer empties so that only [empty] bytes remain the LK202-25 will return an "almost empty" message (0xFF) to the controller.

The LK202-25 will return the "almost full" message for every byte sent to the LK202-25 until the used buffer space once more drops below the [full] level.

Whether the user is in 'Flow Control Mode' or not, the module will ignore display or command bytes which would overrun the buffer. While in 'Flow Control Mode' the unit will return 0xFE when buffer is almost full even though it may have already thrown rejected data away. The buffer size for the LK202-25 is 80 bytes.

When using this command in an application, selection of the value for the buffer almost full should be considered very carefully. This is a critical aspect of using this command to it's full potential. When using a host system or PC which contains a FIFO, the user should set the value of [full] equal to or greater than the size of the FIFO. The reason for this is that the FIFO may be full when the host system receives 0xFE. In the case of 16550 UART the size at its maximum is 16, therefore the value of should be set to 16 or greater.

### 6.2.2 Exit Flow Control Mode (254 59)

This command turns off flow control. Bytes may overflow the buffer without warning.

## 7. Appendix: Command Summary

### 7.1 General

The operation of the LK202-25 is controlled by a simple and consistent command set. Commands control

- text display
- graphics display
- keypad interface
- miscellaneous operating parameters

This chapter includes summary tables of all commands. Individual commands are discussed in detail in Chapters 3 to 5 in the same sequence as in the following tables.

### 7.2 Issuing Commands

Commands are issued to the LK202-25 by the controller. In a test setup, commands can be issued to the LK202-25 by means of a BASIC program, using the `chr$( )` function. In the tables below, we've shown commands in hex, ASCII and decimal form. All commands begin with the prefix character `0xFE` (254 decimal). These commands are issued on the serial communications link (I<sup>2</sup>C or RS-232) at the currently defined baud rate.

For example (using BASIC in a test setup), you could issue the command to clear the screen on the LK202-25 by including the line:

```
PRINT#1,chr$(254);chr$(88)
```

in your BASIC program.

### 7.3 On Numbers

Like all computerized devices, the LK202-25 operates with commands and values in the form of binary numbers. These binary numbers are arranged in 8 digit (i.e. 8 bit) groups called bytes. The decimal value of a byte may have any value from 0 to 255.

Bytes are usually specified in either decimal or hexadecimal (base 16) form for convenience, since binary numbers are confusing to deal with directly. Hexadecimal (hex) numbers are particularly convenient because exactly two hexadecimal digits make up one byte, each hex digit representing 4 binary digits (4 bits) as shown here:

Binary	Hex	Decimal	Binary	Hex	Decimal
0000	0	0	1000	8	8
0001	1	1	1001	9	9
0010	2	2	1010	A	10
0011	3	3	1011	B	11
0100	4	4	1100	C	12
0101	5	5	1101	D	13
0110	6	6	1110	E	14
0111	7	7	1111	F	15

Based on the table, the byte 01001011 can be represented in hex as 4B, which is usually written as any of 4Bh, 4BH, 4B hex or 0x4B.

The numbers can also be expressed in decimal form if preferred.

### 7.3.1 ASCII Characters

Since computers deal internally with numbers only, but externally with both letters and numbers, several schemes were developed to "map" written characters to numeric values. One such scheme has become universal, the American Standard Code for Information Interchange, or ASCII. ASCII tables are readily available from a number of sources. A few examples will do here:

The letter	A	has a value of	65 decimal or	41 hex
The letter	a	has a value of	97 decimal or	61 hex
The number	0	has a value of	48 decimal or	30 hex
The number	9	has a value of	57 decimal or	39 hex

This gives rise to the possibility of confusion when parameters are being set on the LK202-25. For example, the GPO ON and OFF commands use a number to indicate which GPO is being controlled. We're told that acceptable values are 0 to 6. **All such parameters must use numeric values (i.e. the actual byte values).** If we send the ASCII number 0 by mistake it will actually give the value 48 decimal (30 hex) to the parameter, which is wrong.

In the tables given in the following sections ASCII characters are shown as 'A', with single quotes.

## 7.4 Text Commands

See Chapter 3 for command descriptions. Syntax in the tables below is given in hex, decimal and decimal with ASCII, in that order, one per line.

Note: The letter "R" in the Default column indicates that this state can be saved to nonvolatile memory with the Remember command. See section 6.1.1.

Table 7-1 Text Commands

Command	Syntax	Default	Notes
Auto line wrap on	FE 43 254 67 254 'C'	on R	Enables line wrapping (not word wrap).
Auto line wrap off	FE 44 254 68 254 'D'	on R	Disables line wrapping.
Auto scroll on	FE 51 254 81 254 'Q'	off R	Enables scroll at bottom of screen. Text will push display up one line to make room for new line.
Auto scroll off	FE 52 254 82 254 'R'	off R	Disables auto scroll. Text will wrap to top left and overwrite existing text.
Set cursor position	FE 47 [col] [row] 254 71 [col] [row] 254 'G' [col] [row]	n/a	Moves cursor to the specified column and row. <b>The cursor marks the text insertion point in this and all commands.</b>

Command	Syntax	Default	Notes
Send cursor home	FE 48 254 72 254 'H'		This command moves the cursor to the top left of the display area.
Underline cursor on	FE 4A 254 74 254 'J'	off R	Turns on the underline cursor.
Underline cursor off	FE 4B 254 75 254 'K'	R	Turns off the underline cursor.
Block cursor on	FE 53 254 83 254 'S'	on R	Turns on the blinking block cursor.
Block cursor off	FE 54 254 84 254 'T'	R	Turns off the blinking block cursor.
Cursor left	FE 4C 254 76 254 'L'		Moves the cursor one position to the left. If the cursor is already at the beginning of a line it will move to the end of the other line.
Cursor right	FE 4D 254 77 254 'M'		Moves the cursor one position to the right. If the cursor is already at the end of a line it will move to the beginning of the other line.

## 7.5 Keypad Interface Commands

Note: The letter "R" in the Default column indicates that this state can be saved to nonvolatile memory with the Remember command. See section 6.1.1.

Table 7-2 Keypad Interface Commands

Command	Syntax	Default	Notes
Auto repeat mode on	FE 7E [0x00][0x01] 254 126 [0]1 254 '~' [0]1	off R	Applies to keypad only. 0x00 = 200 ms typematic, 0x01 = key down/key up codes sent.
Auto repeat mode off	FE 60 254 96 254 ''	off R	Applies to keypad only.
Auto transmit key presses on	FE 41 254 65 254 'A'	on R	Sets auto transmit mode for keypad. Key presses are transmitted to host without polling.
Auto transmit key presses off	FE 4F 254 79 254 'O'	off R	Up to 10 key presses buffered until polled.
Clear key buffer	FE 45 254 69 254 'E'	n/a	Clear unread key presses.

Command	Syntax	Default	Notes
Poll keypad	FE 26 254 38 254 '&'	n/a	Returns buffered key presses to application. Returns 0x00 if no key presses. High order bit set unless this is the last/only key press.
Set debounce time	FE 55 [time] 254 85 [time] 254 'U' [time]	52 ms R	Resolution: 1 = 0.6554 ms [time] is a numeric multiplier.

## 7.6 Bar Graphs and Special Characters

The commands in this section are used to define and display bar graphs and special characters.

*Table 7-3 Bar Graph and Special Character Commands*

Command	Syntax	Notes
Initialize thick vertical bar graph	FE 76 254 118 254 'v'	Initializes the user character set to make wide vertical bar graphs.
Initialize thin vertical bar graph	FE 73 254 115 254 's'	Initializes the user character set to make narrow vertical bar graphs.
Initialize horizontal bar graph	FE 68 254 104 254 'h'	Initializes the user character set to make horizontal bar graphs.
Define custom character	FE 4E [c][8 bytes] 254 78 [c][8 bytes] 254 'N' [c][8 bytes]	Defines one of 8 custom "user" characters. Character number is [c] between 0x00 and 0x07. The 8 bytes are described in section 5.1.6.
Draw vertical bar graph	FE 3D [col][length] 254 61 [col][length] 254 '=' [col][length]	Draws a vertical bar graph at column [col] of length [length]. Length is measured in pixels (0x00 to 0x14). User must first use the 'v' or 's' command to initialize characters.
Draw horizontal bar graph	FE 7C [c][r][d][length] 254 124 [c][r][d][length] 254 ' ' [c][r][d][length]	Draws a horizontal bar graph starting at column [c] on row [r] with direction [d] (0 is right, 1 is left) of length [length]. Length is measured in pixels (0x00 to 0x64 if starting in column 1). User must first use the 'h' command to initialize characters.

## 7.7 Miscellaneous Commands

Note: The letter "R" in the Default column indicates that this state can be saved to nonvolatile memory with the Remember command. See section 6.1.1.

Table 7-4 Miscellaneous Commands

Command	Syntax	Default	Notes
Remember	FE 93 [0 1] 254 147	off	Turns the "remember" function on [1] or off [0].
Clear display	FE 58 254 88 254 'X'	n/a	Clears screen of text and graphics, places text cursor at top left.
Set contrast	FE 50 [contrast] 254 80 [contrast] 254 'P' [contrast]	0x80 128	Sets display contrast. Compensates for viewing angle. Contrast is a value between 0 and 255 (hex 0 to FF). Larger = darker.
Set contrast and save	FE 91 [contrast] 254 145 [contrast]	0x80 128	Same as "set contrast" but saves [contrast] as default.
Backlight on	FE 42 [minutes] 254 66 [minutes] 254 'B' [minutes]	on R	Backlight will stay on for [minutes]. If [minutes] = 0 backlight will stay on permanently.
Backlight off	FE 46 254 70 254 'F'	on R	Turns off backlight.
Load startup screen	FE 40 [40 char] 254 64 [40 char] 254 '@' [40 char]	Matrix Orbital LK202-25	Loads new startup screen (40 characters). Screen is remembered for subsequent power ups.
General purpose output off	FE 56 [gpo #] 254 86 [gpo #] 254 'V' [gpo #]	off	Turns a general purpose output OFF. [gpo #] may be from 1 to 6. See section 2.2 for further details.
General purpose output on	FE 57 [gpo #] 254 87 [gpo #] 254 'W' [gpo #]	off	Turns a general purpose output ON. [gpo #] may be from 1 to 6. See section 2.2 for further details.
Set I <sup>2</sup> C address	FE 33 [address] 254 51 [address] 254 '3' [address]	0x50	Value is write address and must be even, read address is 1 higher.
Read module type	FE 37 254 55 254 '7'	see table	Reads the module type. See table in section 6.1.11.
Set RS232 port speed	FE 39 [speed] 254 57 [speed] 254 '9' [speed]	19,200 baud	Sets RS232 speed. See table in section 6.1.12 for values of [speed]
Set Serial Number	FE 34 [byte1][byte2] 254 52 [byte1][byte2] 254 '4' [byte1][byte2]		This is a one-time-use command which works only on units without factory set serial numbers.
Read Serial Number	FE 35 254 53 254 '5'		Reads the two byte serial number of the module.

<b>Command</b>	<b>Syntax</b>	<b>Default</b>	<b>Notes</b>
Read Version Number	FE 36 254 54 254 '6'		Reads the firmware version number of the module.
Enter flow control mode	FE 3A [full] [empty] 254 58 [full] [empty] 254 ':' [full] [empty]	off	Sets "full" and "empty" marks for the 80 byte display buffer. When buffer reaches [full] display will return 0xFE to host. When buffer reaches [empty] display will return 0xFF.
Exit flow control mode	FE 3B 254 59 254 ';'		Turns off flow control.

## 8. Appendix: Specifications and Options

### 8.1 Specifications

<b>Environmental Specifications</b>		
	Standard Temperature	Extended Temperature
Operating Temperature	0°C to +50°C	-20°C to +70°C
Storage Temperature	-20°C to +70°C	-40°C to +85°C
Operating Relative Humidity	90% max non-condensing	90% max non-condensing

<b>Electrical Specifications</b>	
Supply Voltage	4.75 - 5.25 Vdc (optional 8 – 15 VDC)
Supply Current	9 mA typical
Supply Backlight Current	115 mA typical

<b>Optical Characteristics</b>	
Number of Characters	40 (20 characters by 2 lines)
Matrix format	5 x 7 with underline
Display Area	82.2 x 18.20 mm XxY
Character Size	3.20 x 5.55 mm (XxY), not including underline
Character Pitch	3.7 mm
Line pitch	5.95 mm
Dot Size	0.60 x 0.65 mm (XxY)
Dot Pitch	0.65 x 0.70 mm (XxY)
LED Backlight Life	100,000 hours typical
Color of Illumination	Yellow Green




Figure 8-1 Physical Layout

## 8.2 Options

Options Available on LK202-25	
Extended Temperature	E
Wide Voltage	V

## 9. Appendix: Glossary

<b>ASCII</b>	American Standard Code for Information Interchange. A 7 bit binary code representing the english alphabet, decimal numbers and common punctuation marks. "Also includes control characters" such as carriage return or end of text. An 8 bit superset of the standard ASCII codes is often used today to include foreign characters and other symbols. These supersets are often called extended ASCII character sets.
<b>Backlight</b>	A backlit display is illuminated from behind to provide nighttime and improved daytime readability.
<b>Baud Rate</b>	The (data and signaling) bit transmission rate of an RS232 device.
<b>Binary Number</b>	A number written using binary notation which only uses zeros and ones
<b>Bit</b>	The smallest unit of information a computer can work with. Each bit is either 0 or 1. Binary digit.
<b>Bitmap</b>	A representation, consisting of rows and columns of dots, of a graphics image in computer memory. The value of each dot (whether it is filled in or not) is stored in one or more bits of data.
<b>Byte</b>	A grouping of eight binary bits
<b>CCFL</b>	Cold Cathode Fluorescent Lamp. A high brightness backlighting source consists of a fluorescent tube powered by a high voltage A.C. source.
<b>Configuration</b>	The way a system is set up, or the assortment of components that make up the system. Configuration can refer to either hardware or software, or the combination of both.
<b>Contrast</b>	The ratio of luminance between the light state of the display to the dark state of the display.
<b>Controller</b>	The microcontroller or PC used to control the Matrix Orbital display unit.
<b>DB-9</b>	The designation of a connector used in the RS232 interface: 9 pin connector
<b>Firmware</b>	Software (programs or data) that has been written onto read-only memory (ROM). Firmware is a combination of software and hardware. ROMs, PROMs and EPROMs and flash EEPROMs that have data or programs recorded on them are firmware.
<b>Font</b>	A design for a set of characters. A font is the combination of typeface and other qualities, such as size, pitch, and spacing.
<b>Font Metric</b>	A definition of where font is to be placed, such as margins and spacing between characters and lines.
<b>Hexadecimal</b>	Refers to the base-16 number system, which consists of 16 unique symbols: the numbers 0 to 9 and the letters A to F. For example, the decimal number 15 is represented as F in the hexadecimal numbering system. The hexadecimal system is useful because it can represent every byte (8 bits) as two consecutive hexadecimal digits. It is easier for humans to read hexadecimal numbers than binary numbers.
<b>I<sup>2</sup>C</b>	Short for Inter-IC, a type of bus designed by Philips Semiconductors in the early 1980s, which is used to connect integrated circuits (ICs). I <sup>2</sup> C is a multi-master bus, which means that multiple chips can be connected to the same bus and each one can act as a master by initiating a data transfer.
<b>Interface</b>	A means by which two systems interact.

<b>LCD</b>	Liquid Crystal Display
<b>Module Type Value</b>	This refers to the model number of the module.
<b>Pixel</b>	The smallest individually controllable element of a display.
<b>Pre-Generated Fonts</b>	Pre-determined fonts which can be downloaded into graphic liquid crystal displays.
<b>Primitive</b>	A low-level object or operation from which higher-level, more complex objects and operations can be constructed. In graphics, primitives are basic elements, such as lines, curves, and polygons, which you can combine to create more complex graphical images
<b>RS-232</b>	Short for recommended standard-232C, a standard interface approved by the Electronic Industries Association (EIA) for connecting serial devices.
<b>Scroll</b>	To view consecutive lines of data on the display screen. The term scroll means that once the screen is full, each new line appears at the bottom edge of the screen and all other lines move up one position.
<b>Serial Number</b>	A number that is one of a series and is used for identification of the module
<b>Serial Port</b>	A port, or interface, that can be used for serial communication, in which only 1 bit is transmitted at a time.
<b>Version Number</b>	This refers to the firmware revision number of the module.
<b>Volatile Memory</b>	Temporary memory. Once the power supply is turned off volatile memory is then erased.

## 10. List of Distributors

### North America

#### Canada

##### [HVW Technologies](#)

Suite 473, 300 - 8120 Beddington Blvd. NW  
Calgary, Alberta, Canada T3K 2A8  
Telephone: +1 403 730 8603  
Facsimile: +1 403 730 8903  
Email: [info@hvwtech.com](mailto:info@hvwtech.com)

##### [Tri-M Systems Inc.](#)

6-1301 Ketch Court  
Coquitlam, BC V3K 6X7 Canada  
Toll Free Telephone: 800-665-5600  
Alternate Telephone: 604-527-1100  
Facsimile: 604-527-1110  
Email: [info@tri-m.com](mailto:info@tri-m.com)

#### United States

##### [EMJ Embedded Systems](#)

Suite 100-1434 Farrington Road  
Apex, North Carolina, USA, 27502  
Toll Free Telephone: 1 800 436 5872  
Facsimile: +1 919 363 4425  
Email: [sales@emjembedded.com](mailto:sales@emjembedded.com)

##### [Jameco Electronic Components](#)

1355 Shoreway Road  
Belmont, California, USA, 94002-4100  
Toll Free Telephone: 1 800 831 4242  
Toll Free Facsimile: 1 800 237 6948  
Email: [sales@jameco.com](mailto:sales@jameco.com)  
Carries a selection of Matrix Orbital Displays for more information visit the Official Jameco Website.

##### [Linux Central](#)

Suite T2 37060 Garfield  
Clinton Township, Michigan, USA, 48036  
Telephone: +1 810 226 8200  
Toll Free Telephone: 1 877 LINUX CD (546 8923)  
Facsimile: +1 810 226 8600  
Email: [sales@linuxcentral.com](mailto:sales@linuxcentral.com)

#### United States (continued)

##### [BiPOM Electronics Inc](#)

11246 South Post Oak #205  
Houston, Texas, USA, 77035  
Telephone: +1 713 661 4214  
Facsimile: +1 713 661 4201  
General Information: [info@bipom.com](mailto:info@bipom.com)  
Technical Support: [tech@bipom.com](mailto:tech@bipom.com)  
Sales: [sales@bipom.com](mailto:sales@bipom.com)

##### [Hicotech](#)

Suite 9, 2000 Wyatt Drive  
Santa Clara, CA 95054, USA  
Telephone: +1 408 748 9971  
Facsimile: +1 408 748 9973  
Email: [info@hicotech.com](mailto:info@hicotech.com)  
Note: Specializes in distribution of Korea.

### Europe

#### Austria

##### **MEGATON Ges.m.b.H.**

Franz-Schubert-Gasse 12  
A-2372 GIESSHÜBL  
Telephone: +4 0 2236 43179  
Facsimile : +43 0 2236 431792  
Email: [oesterreich@elektronikladen.de](mailto:oesterreich@elektronikladen.de)

#### Belgium

##### [Antratek Electronics](#)

Cipalstraat 3,  
2440 Geel Belgium  
Telephone: +32 14 570557  
Facsimile: +32 14 570556  
Email: [info@antratek.com](mailto:info@antratek.com)

#### Finland

##### [Symmetric Oy](#)

Maria Jotunin Tie 11  
Helinski, Finland 00400  
Telephone: + 358 9 5885 322  
Facsimile: + 358 9 5885 578  
Email: [symmetric@symmetric.fi](mailto:symmetric@symmetric.fi)

## Europe (continued)

### Germany

#### [Elektronikladen Mikrocomputer Gmbh](#)

Offices throughout Germany  
Head Office: Wilhelm - Mellies - STR. 88,  
D - 32758, Detmold  
Telephone: +49 0 5232 8171  
Facsimile : +49 0 5232 86197  
Email: [sales@elektronikladen.de](mailto:sales@elektronikladen.de)

### Italy

#### [Qnet](#)

Via Circonvalazione Sud, 76  
Codriopo, Udine, Italy, 33033  
Telephone : +39 0 432 906062  
Facsimile : +39 0 432 901514  
Email: [info@qnet.it](mailto:info@qnet.it)

### The Netherlands

#### [Antratek Electronics](#)

Kanaalweg 33,  
NL-2903LR Capelle aan den IJssel  
The Netherlands  
Telephone : +31 10 4504949  
Facsimile: +31 10 4514955  
Email: [info@antratek.nl](mailto:info@antratek.nl)

### Scandinavia

#### [Lawicel](#)

Klubbgatan 3  
SE-282 32 Tyringe, Sweden  
Telephone: +46 0 451 598 77  
Facsimile: +46 0 451 598 78  
Email: [info@lawicel.com](mailto:info@lawicel.com)

#### [Lilla Fabriken](#)

Box 1003  
SE-172 21 Sundbyberg, Sweden  
Telephone: +46 8 287 286  
Facsimile: +46 8 288 802  
Email: [info@lillfab.se](mailto:info@lillfab.se)

### Switzerland

#### **Bernhard Elektronik**

Aarau Str. 20,  
CH-5734 Reinach AG  
Telephone : +41 0 62 7716944  
Facsimile : +41 0 62 7716944  
Email : [schweiz@elektronikladen.de](mailto:schweiz@elektronikladen.de)

## Middle East

### Israel

#### **Alpha Terminals & Printers Ltd.**

7 Ha'Mifalm St.  
Petach - Tikva, Israel 49250  
Telephone: +972 3 9214422  
Facsimile: +972 3 9219966  
Email: [alpha99@ibm.net](mailto:alpha99@ibm.net)

## Australia

#### [Alfa-Tek](#)

Unit 7, 42 - 50 Stud Road  
Bayswater, Victoria, Australia, 3111  
Telephone: + 61 39 720 5344  
Facsimile: + 61 39 720 5268  
Email: [tim@alfatek.com.au](mailto:tim@alfatek.com.au)

## Asia

### India

#### [AL Systems](#)

105 3rd Street  
Tatabad Coimbatore - 641 012.  
Tamil Nadu, India.  
Telephone: +91 422 233 166  
Alternative Telephone: +91 422 493 960  
Facsimile: +91 422 213 849  
Email: [alsystem@md2.vsnl.net.in](mailto:alsystem@md2.vsnl.net.in)

## Africa

### Egypt

#### **AmGroup 13**

Sheraton Heliopolis  
Zone 8, Cairo EGYPT  
Email: [amgrou@link.com.eg](mailto:amgrou@link.com.eg)

